

FINISH LEGEND							
FINISH LEGEND							
Code	Rev. Date	Manufacturer	Pattern	Color	Details	Remarks	
DIVISION 06: WOODS, PLASTICS, AND COMPOSITES							
062023 Interior Finish Carpentry							
WD-1 - WD-3 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
WD-4		Tague Lumber or Equal	WM412	Match Existing	11/16" x 3 1/2"	Window & Door Casing	
WD-5		Dimensional Lumber		Stained to match CAB-1	1" x 2"	Reception desk trim	
064100 Architectural Wood Casework							
Wood-Veneer-Faced Casework (As noted on Interior Elevations as - WOOD VENEER ARCH CASEWORK)							
CAB-1		Merrillat Classic		Maple Stained - Basalt	Full overlay door, Decorative hardware by Colonial Bronze 745, 746, 844 Pull Series in Satin Brass	Clocktower Lobby	
Plastic-Laminate-Clad Casework (As noted on Interior Elevations as - PLAM ARCH CASEWORK)							
PL-1 - PL-8 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
PL-9		Wilsonart	7964K-12	Skyline Walnut	Decorative hardware by Colonial Bronze 745, 746, 844 Pull Series in Satin Brass	Security Room	
066400 Plastic Paneling							
FRP-1		Panolan FRP	Embossed	Silver; Thickness: 0.09 Class A	Full height panels with matching trims an...	Temporary Kitchen	
DIVISION 09: FINISHES							
095113 Acoustical Panel Ceilings							
ACT-1, ACT-3 & ACT-4 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
ACT-2		Armstrong	Kitchen Zone	White	2'x4' Square Lay-In; 15/16" Prelude Grid White	Temporary Kitchen	
ACT-5		Armstrong	Cortega - Fisured	White	2'x4' Square Lay-In; 15/16" Prelude XL Grid White	BOH	
ACT-6 - ACT-11 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
ACT-12		Match Existing				Temporary Gym	
095513 Resilient Base and Accessories							
RB-2 - RB-4 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
RB-1		Tarkett	Inflexion	Iceide 08	6"H	General	
RB-5		Tarkett	Traditional Cove	Grey Haze 24	4"H, Coil	FACP, Package Room, Temporary PT/OT & Gym	
DS-5		Johnsonite	CTA Wheeled Traffic Transition	Dark Gray	At height appropriate for smooth transition from one material to another. Johnsonite outfloor leveler to be used in conjunction as needed to ensure a flush condition between adjacent materials of different heights.	Flooring Transition from Existing (VCT) to Resinous Epoxy Floor (RES)	
095516 Resilient Sheet Flooring							
RF-2 - RF-5 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
RF-6		Mannington	Assurance III	Cremello	6 or 12" wide with matching heat weld seams	PT/OT, Package Room	
095519 Resilient Tile Flooring							
RF-1		Patcraft	Woodtone 1724V	Bark V2 00530	9" x 36"; 20mil wear layer	General	
RF-2 - RF-5 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
095723 Resinous Flooring							
RES-1		JeRocK		TBD		Temporary Kitchen	
096813 Tile Carpeting							
CPT-1 - CPT-9 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
CPT-10		Patcraft	Harmonious	Aspire 00450	18" x 36", Multi-Level Pattern Cut,Loop, 28 oz, 100% Solution Dyed, Brick installation. Moisture Barrier Backing. *Product to be purchased and installed by owner	Clocktower Corridor Carpet	
CPT-11 - CPT-19 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
CPT-20		Patcraft	Harmonious	Noteworthy 00110	18" x 36", Multi-Level Pattern Cut,Loop, 28 oz, 100% Solution Dyed, Brick installation. *Product to be purchased and installed by owner	4th Floor Staff Room	
CPT-21		Patcraft	Urban Relief - Edgeland I0517	Subway 00525	24" x 24"	Temporary Gym/Fitness	
097200 Wall Covering							
WC-1 - WC-17 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
WC-18		Koroseal	Paradox	Future PR21-II	54"W, 20oz, Type II Vinyl. Provide two (2) rolls of attic stock upon completion of the project.	Clocktower Lobby	
099123 Interior Painting							
P-1		Sherwin Williams	SW7006	Extra White	ProMar 200 Semi-gloss	General Trim	
P-2		Sherwin Williams	SW7757	High Reflective White	ProMar 200 Flat	General Ceiling	
P-3		Sherwin Williams	SW7043	Worldly Gray	ProMar 200 Eggshell	General Wall Paint	
P-4		Sherwin Williams	SW9143	Cadet	ProMar 200 Eggshell	Clocktower Lobby	
P-5 - P-14 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
P-14		Sherwin Williams	SW0020	Peacock Plume	ProMar 200 Eggshell	Temporary Gym	
P-15 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes							
P-16		Sherwin Williams	SW6354	Armagnac	ProMar 200 Eggshell	Temporary PT/OT	
P-17		Sherwin Williams	SW6422	Shagreen	ProMar 200 Eggshell	Temporary PT/OT	
P-18		Sherwin Williams	SW6473	Surf Green	ProMar 200 Eggshell	Temporary PT/OT	
DIVISION 10: SPECIALTIES							
102123 Cubicle Curtains And Track							
CC-1		Arc-Com	Rue Clear AC-33352	Jade #3	72/74 Width, ~ 21.25"V Repeat, 18" Mesh top color to match curtain. Ceiling mounted track color white	Temporary PT/OT	
102600 Wall and Door Protection							

FLOOR TRANSITION SCHEDULE			
DS-4			
DS-5			
* CARPET TILE TO RESILIENT PLANK SHALL BE A BUTT SEAM			
TRIM PROFILES			
RB-1		RB-5	
WD-4			
CROWN MOLDING MATCH EXISTING PROFILE			
EDGE PROFILES			
QUARTZ & SOLID SURFACE EASED EDGE DETAIL		1/4\"/>	
FLOOR BASE DETAILS			
FINISHED FACE OF WALL		FINISHED FACE OF WALL	
RUBBER COVE BASE		RUBBER STRAIGHT BASE	
SEALED EDGE			
HARD SURFACE FLOORING			
RESILIENT FLOORING			
ADHESIVE			
FRP			
COVE CAP 2-BAR INSTALL TO SPEC			
CLEAR SILICONE SEALANT			
RESINOUS COVE BASE			
RAPID WELD OR CORNER ROD			
RESINOUS FLOORING INSTALL OVER EXISTING			
RESINOUS TO FRP			
FINISH LEGEND CONTD.			
CG-1 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes			
CG-2	InPro	Storm Cloud 0372	2\"/>
CG-3	InPro	Designer White 0101	2\"/>
DIVISION 12: FURNISHINGS			
123661 Simulated Stone Countertops			
SS-1 - SS-3 are not used in Enabling portion of project. Refer to Pavilion Finish Legend for finishes			
SS-4	Corian	White Onyx	Price Group 5, 1/2\"/>
QZ-1	Cambria	Skara Brae	Matte Finish, 3cm Thick with Treeline Edge (Bevel)

GENERAL ID NOTES		
1. FINISHES ARE SHOWN ON A2 SERIES.		
GENERAL ID NOTES		
1. REFER TO FINISH LEGEND FOR MATERIAL SPECIFICATION.		
2. REFER TO FINISH PLANS AND ELEVATIONS FOR EXTENTS OF FLOOR PATTERNS, WALL FINISHES AND CABINET MATERIALS.		
3. ALL PRODUCTS / MATERIALS TO BE SOURCE FROM SAME LOTS TO ENSURE COLOR MATCH.		
4. ALL PRODUCTS INSTALLED PER MANUFACTURERS REQUIREMENTS.		
5. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXTENTS OF MATERIALS IN THE FIELD WITH EXISTING CONDITIONS AND ADVISE THE ARCHITECT OF ANY CONFLICT.		
6. CONTRACTOR TO COORDINATE MEP REQUIREMENTS WITH ALL NEW EQUIPMENT/FIXTURES AS WELL AS WITH RE-USED EXISTING EQUIPMENT.		
7. ALL SURFACES WHERE EXISTING FINISHES ARE TO BE REMOVED ARE TO BE REPAIRED TO QUALITY FINISH OF ADJACENT SURFACE.		
8. EXISTING MATERIALS TO BE REUSED ARE TO BE PROTECTED, AND PREPARED TO RECEIVE NEW FINISH.		
9. ALL PAINT TO BE EGGSHELL FOR WALLS U.N.O., FLAT FINISH FOR CEILING U.N.O., & SEMI-GLOSS FOR TRIM U.N.O.		
10. CORNER GUARDS TO BE INSTALLED FULL HEIGHT U.N.O. INSTALL (CG1) AS INDICATED ON FINISH PLAN.		
11. TOE KICK SHALL MATCH CABINET FINISH.		
12. ALL EXPOSED END PANELS, BACK PANELS AND INTERIOR SIDE PANELS SHALL BE FINISHED TO MATCH CABINETS.		
13. ALL MECHANICAL, ELECTRICAL PANELS, DIFFUSERS & GRILLES ARE TO BE PAINTED TO MATCH ADJACENT FINISH IN PUBLIC/COMMON AREAS.		
14. FINISHES NOTES IN CORRIDORS ARE TYPICAL CONDITIONS THAT ARE TO BE USED THROUGH REMAINING CORRIDOR.		
15. ALL TRIM ON WINDOWS, DOORS AND WALL TO BE PAINTED P1, U.N.O. REFER TO DOOR SCHEDULE FOR DOOR FINISH.		
16. REMOVE ALL EXISTING WALL PAPER/COVERING & BORDERS. PREPARE WALL TO RECEIVE PAINT AT LEVEL 5 FINISH QUALITY.		
17. ALL ARCHITECTURAL MILLWORK AND RESIDENTIAL CASEWORK TO HAVE DECORATIVE HARDWARE AS NOTED IN FINISH LEGEND PER CAB OR PLAM SPECIFICATION.		
18. ALL DOOR HARDWARE TO BE SATIN NICKEL FINISH, U.N.O. .		
19. REFER TO REFLECTED CEILING PLANS FOR EXTENT OF CROWN MOLDING.		
20. ANY EXPOSED PIPING AND GRILLES TO MATCH ADJACENT WALL FINISH.		
21. CONTRACTOR TO DETERMINE THE APPROPRIATE HEIGHT PRODUCT FOR THE TRANSITIONING MATERIALS HEIGHT IN ORDER TO HAVE A FLUSH TRANSITION.		
22. TRANSITIONS ARE TO BE USED WITH A CONCEALED RUBBER SUBFLOOR LEVELER SYSTEM SCORED AT APPROPRIATE DEPTH FOR SMOOTH, FLUSH TRANSITION FROM ONE MATERIAL TO ANOTHER.		
23. SEAM SEAL CARPET EDGE AT TRANSITION.		
24. REFER TO LEGEND FOR TRANSITION FINISH SELECTION.		
Professional Certification. I hereby certify that these documents were prepared or approved by me, and that I am a duly-licensed registered architect under the laws of the State of Maryland, License No. 21272, Expiration Date: 9/26/2026.		
PROJECT TITLE		
Collington		
A KENDAL AFFILIATE		
ENABLING RENOVATION CONSTRUCTION DOCUMENTS		
SFCS		
Architecture Engineering Planning Interiors		
SFCS Inc. • 305 South Jefferson Street Roanoke, Virginia 24011.2003 540.344.6664 • Fax 540.343.6925 www.sfcs.com		
DESIGNER : JGB	DRAWN : JMS	
ARCHITECT : EMJ	CHECKED : MTA	
ENGINEER : -	APPROVED : JGB	
NO.	REVISION DESCRIPTION	DATE
DRAWING TITLE		
GENERAL NOTES, FINISH KEY, ABBREVIATIONS, AND FINISH LEGEND		
DATE: MAY 28, 2026	DRAWING	
COMM. NO. 18135.00		
10.00-1A		