Incoming Fire and Domestic Water Service Mark-up until Civil Drawings are provided.

Assume existing water line is 6' below sidewalk grade and assume Utility Room floor is 10' below sidewalk grade.

- Package 31A to own bringing utilities from street and stubbing into the Utility Room 002.
- Package 22A owns connecting Fire Line from stub to double-check backflow preventer (including install of preventer), and owns connecting to domestic water stub and beyond (ref. Plumbing drawings)
- Package 21A owns Fire Line from double-check backflow preventer and beyond to provide complete sprinkler/fire protection system (ref. Fire Protection and Alarm drawings).

